TREE PROTECTION PLAN CHECKLIST

INFORMATION CHANGES FREQUENTLY: PLEASE CHECK ATLANTAGA.GOV FOR UPDATES AND CURRENT ADVISORIES

Arborists Plan Reviewer:							
Sean Gaynor 404-865-8810	Marty Ussery 404-330-6019	Barrie Collins 404-330-6176	Monique Humphrey 404-330-6076				
Commercial Plan Reviewer	Light Commercial Plan Reviewer	Residential Plan Reviewer	Residential Plan Reviewer				
D. Califfrage							

DCI	11110113.
	Boundary Tree — All hardwood trees >=6"DBH, or pines >=12"DBH that have some portion of the main trunk directly on the property boundary, or a qualifying tree on the adjacent property, whose critical root zone and /or structural root plate intrudes across the property line and limit of disturbance.
	Caliper - diameter of new tree (nursery stock) trunk at 6" above ground level.
	CRZ - Critical Root Zone: a circle having a radius of one foot for each one inch of tree DBH. Diameter is twice the size of radius. If the CRZ is unobstructed by root barriers it can also be referred to as "Gross CRZ". Formula to calculate area of a circle is (pi (3.14) x radius squared).
	Destroyed Tree — if the CRZ is impacted 20% to 33% and the Structural Root Plate is not protected by the tree protection fence, or if the CRZ is impacted more than 33%.
	Net Critical Root Zone — in urban environments the root zone is sometimes obstructed with root barriers, i.e. public roads and building foundations. When this occurs, the root zone is reduced in size. The reduction in the root zone is called the Net Critical Root Zone.
	• DBH - Diameter at Breast Height: the width of tree trunk measured at 4.5' feet above ground level. Tree trunks having more than one trunk at 4.5' must be measured and labeled individually and added together. The total DBH is to be used to label the tree on the Tree Protection Plan. Example; 1 tree with two trunks would be labeled, 12"/16" HWD.
	• Structural root plate - means the zone of rapid root taper that provides the tree stability against wind throw. The radius of the root plate is proportional to the stem diameter (DBH) of a tree. The table below provides examples of

DBH(inches)	6-7"	8"	9-11"	12-14"	15-19"	20-24"	25-31"	32"	33-38"	39-48"
SRPdistance(radius')	5′	5.5'	6′	7'	8′	9'	10′	10.5′	11"	12'

root plate radii for upright trees without restricted roots.

No Trees Impacted:

A plan may be approved as 'No Trees Impacted' if there are no trees whose Critical Root Zone are impacted by the demolition work limit. If there are no trees that can be shown on the drawing, submit several panoramic pictures showing all sides of the structure. The pictures should be submitted with the plans along with a signed No Trees Impacted Statement.



Plan Checklist - show and label the following elements (Tree Protection Plan - Sec. 158-105(a))

- 1. Provide three (3) copies of drawings.
- 2. Provide a survey of all trees on property, and on adjacent property, whose critical root zone is impacted by limits of land disturbance. Tree locations must be accurately shown, labeled as HWD (hardwood) or pine, and note their respective DBH. All hardwood trees >= 6" DBH, pines >=12" DBH must be shown on the drawing.
- 3. Tree protection fences must be located at the edge of critical root zone or work limits, whichever provides more tree protection. A tree protection fence can be a 4' orange tree protection fence, but under certain conditions a chain link fence may be required.
- 4. Tree removal and tree replacement plan
- 5. Show an X on the tree symbol for tree(s) proposed to be destroyed.
- 6. Existing topography at 2ft contour intervals.
- 7. Zoning building setbacks
- 8. Site tree data table (see page 4)
- 9. Proposed topography (cut and fill) at 2ft contour intervals.
- 10. Existing* and proposed buildings, structures, driveways, walls, parking areas, and other site improvements.
- 11. Existing* and proposed drainage and water detention structures.
- 12. Existing and proposed underground utilities, i.e. water, gas, electric, sewerage, etc., must be shown from the main line to the house/structure.
 - *NOTE: Existing structures refers to any built structures (including utilities) that will not be demolished prior to redevelopment.
- 13. Dumpster location/Material staging area.
- 14. Proposed trees planted for credit must be at least 2.5" caliper and shown and labeled as to species (from COA recommended tree list). Replacement trees on site are to equal the total number of trees being destroyed, or that can reasonably be expected to be accommodated in a manner which will allow mature growth of the replacement trees. Overstory and mid-canopy trees are required until tree density requirements per zoning district are met. Spacing requirements are measured from existing and proposed trees and to be spaced as follows: Overstory-35ft., Mid Canopy-25ft., Ornamental, Understory, and Screening trees 15ft.
- 15. Critical Root Zone impact calculations: Section 158-105(a)
 - O To calculate the Net Critical Root Zone, measure the area of the CRZ that overlaps roads and structures with foundations. Subtract that area from the total area of the CRZ. Example, a 20" hardwood has a CRZ of 1,256 sf. If the CRZ overlaps a house footprint 230 sf, then the Net CRZ is 1,026 sf. The Net CRZ is the number used to calculate the % impact to the CRZ, which then determines if the tree is considered saved, lost, or destroyed.
 - Must show the CRZ and structural root plate of trees that are impacted or in proximity of disturbance.
 - O To calculate the impact, measure the area of the critical root zone not protected by the tree protection fence and divide it by either the net critical root zone or gross critical root zone; whichever is applicable.
 - a. Saved tree if the CRZ is impacted 20% or less, and the Structural Root Plate is protected by the tree save fence.
 - b. Lost tree if the CRZ is impacted 20% to 33% and the Structural Root Plate is protected by the tree save fence. There are two options if the tree's Structural Root Plate is protected by the tree protection fence and located within the buildable area of the lot:
 - c. Obtain an arboriculture prescription from a certified arborist (International Society of Arboriculture). A contract for the prescription must be presented to the Arborist Plan Reviewer that shows it has been signed and paid. This prescription is in lieu of paying recompense and posting the tree for removal.



- d. Pay recompense for the tree and post for removal. (Not an option if tree is within the setback area of the property.)
- e. Destroyed tree if the CRZ is impacted 20% to 33% and the Structural Root Plate is not protected by the tree protection fence, then the tree must be posted, and recompense calculations must be shown on the drawing.
- f. Destroyed tree if the CRZ is impacted more than 33%. The tree must be posted, and recompense calculations must be shown on the drawing.
- 16. Boundary trees: Sec. 158-105(b)
 - O Boundary trees, whose critical root zone and/or structural root plate intrudes across the property line and limit of disturbance, are required to be shown. They are all hardwood trees >= 6" DBH, pines >=12" DBH on adjacent property.
 - O Boundary trees are required to be protected. They must be located on the site plan, CRZ's shown and impacts calculated.
 - O If a boundary tree is impacted more than 20%, the plans and any prescriptions should be given to the neighbor. A boundary tree agreement signed by the neighbor must be presented to the Arborist Plan Reviewer before preliminary approval can be given. The boundary letter is available in the arborist department and online at https://www.atlantaga.gov/government/departments/city-planning/office-of-buildings/arborist-division
- 17. Trees located in the setback: Sec. 158-102 and Sec. 158-104
 - O Trees located in the setback must be saved unless there is a need for ingress and egress or for the installation of utilities that can't be accomplished in a manner allowing preservation of the tree(s).
 - O Damage to trees located in the setback and required yard is to be minimized to the greatest degree possible.
- 18. Recompense Calculations: Sec. 158-103(b)
 - O Show either Standard Recompense or Maximum Recompense calculations— not both.
 - O The Standard Recompense formula is:
 - O \$100 [(# trees destroyed + # trees lost) # trees replaced] + \$30.00 [(DBH inches destroyed + DBH inches lost) caliper inches replaced]
 - O Maximum Recompense to qualify to use maximum recompense the property must be a vacant lot or new lot of record. Vacant lot means no structure existed on the property for the past 5 years. Also, a percentage of the existing DBH must be retained on site. That percentage is based on the zoning district of the property. See worksheet for zoning district percentages and calculations.
 - **Infrastructure Recompense. Disturbed acreage X \$5,000 = ______
- 19. Lots and subdivisions>one acre: Sec. 158-104 (1)
 - O Environmentally sensitive areas are required to be shown and labeled on the site plan, they include:
 - a. Wetlands, Flood Plains, Streams, mature stands of trees, and other significant aspects of the natural environment
- 20. Parking Lots with 30 or more spaces (existing or proposed): Sec. 158-30
 - O Show barrier curbs
 - O There must be a minimum of 10% landscape area inside the parking lot.
 - O A minimum of one (1) tree/eight (8) parking spaces, show calculations.
 - O Ground cover shall be provided, examples; shrubs, ivy, liriope, pine bark, or other similar landscaping material.



- O Landscape islands are to be a minimum of 36sq ft.; 6 feet long and 6 feet wide.
- O 5-foot minimum green strip between parking lot and public right-of-way. Trees must be planted a maximum of 42.5' on center.

NOTE: Tree density per zoning district on a site must be met regardless of any loss of trees. The requirements are as follows:

R-5 and R-4-A districts: 35 inches per acre R-3, R-3-A, and R-4 districts: 40 inches per acre R-2 and R-2-A Districts: 100 inches per acre

R-1 districts: 150 inches per acre

RG, PD and all other districts: 90 inches per acre

** Is limited strictly to infrastructure as described in Tree Protection Ordinance Section 158.03 (c)(6). Trees proposed to be approved outside of infrastructure limits, will be charged standard recompense.

IMPACTED TREE DATA TABLE

TREE #	DBH	SPECIES	IMPACT %	STATUS	Rcmp.DBH
1	12	PN	22	Saved/P	
2	16	PN	10	Saved	
3	6	HWD	14	Saved	
4	8	HWD	40	Destroy	8
5	32	HWD	100	Destroy	32
6	14	HWD	100	Destroy	14
7	7	HWD	N/A	DDH	
8	30	PN	N/A	DDH	
9	15	PN	15	Saved	
10	24	HWD	15	Saved	
3					54

SUBTOTALS 3

(For viable trees requiring recompense)

NOTES:

- 1. Saved / P = Saved, prescription req'd (20-33% impact)
- 2. Rcmp.DBH. = Recompense DBH
- 3. DDH: Dead, Dying, Hazardous Trees Certified by COA (cite DDH permit # at bottom of this table)
- 4. Destroy: = Destroyed, Recompense req'd (over 33% impact)

